

2002 SPECIFICATION

1105-6 CONSTRUCTION ZONE TRAFFIC CONTROL DEVICE SURVEILLANCE

Provide continuous surveillance operations only during periods of construction activity. Conduct periodic surveillance, each calendar day, during periods of construction inactivity for the following traffic control situations:

- (a) When a change in the travel lane alignment or pattern has been made.
- (b) When a roadway has been closed to traffic and an off-site detour is provided.
- (c) When temporary concrete barrier, drums or other traffic control devices have been placed on or adjacent to a travelway or a shoulder.

1105-7 COMPENSATION.

Payment at the contract unit prices for the various items in the contract will be full compensation for all work covered by this section.

CURRENT SPECIFICATION

1105-6 CONSTRUCTION ZONE TRAFFIC CONTROL DEVICE SURVEILLANCE

The Contractor shall be responsible for the continuous maintenance of all traffic control devices as specified in Sections 1101 and 1105. The Contractor shall conduct surveillance operations periodically each calendar day sufficient to reasonably assure himself and the Engineer that the devices are maintained adequately. Periodic surveillance during periods of construction inactivity shall be conducted for the following traffic control situations:

- (a) When a change in the travel lane alignment or pattern has been made.
- (b) When a roadway has been closed to traffic and an off-site detour is provided.
- (c) When temporary concrete barrier, drums or other traffic control devices have been placed on or adjacent to a travelway or a shoulder.

At times other than specified above, the Contractor will be required to provide continuous surveillance operations only during periods of construction activity.

1105-7 COMPENSATION.

There will be no direct payment for the work covered by this section. Payment at the contract unit prices for the various items in the contract will be full compensation for all work covered by this section.